BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT17828

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/01/2015-16

Improvements to Roads and Drains at Kuvempunagar Ist Stage in Ward No. 11 Vidyaranyapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K ANIL KUMAR	
				In Figures	In Words
1	1243.6	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	75.0	Rupees Seventy Five Only
2	2322	Removing B.S Slab of Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	58.0	Rupees Fifty Eight Only
3	2322	Fixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	75.0	Rupees Seventy Five Only
4	861	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1100.0	Rupees One Thousand One Hundred Only
5	4880	Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WBM, WMM including cleaning of road surface and applying primer at the rate of 0.60 Kg / sqm using mechanical means etc complete as per specifications and directions of engineer in charge of the work	Sqm	31.0	Rupees Thirty One Only
6	122	Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications Clause No. 500.8 complete in all respects as per specifications. with 100-120 TPH capacityH.M.P with sensor paver Gr-II (25 mm to 30 mm) with 5 % VG-30 Bitumen etc complete as per specifications and directions of engineer in charge of the work	Cum	8000.0	Rupees Eight Thousand Only
7	184.5	Providing and laying in position plain cement concrete of proportion 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.8 cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of work	Cum	4847.0	Rupees Four Thousand Eight Hundred Forty Seven Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

20/5/16

8	153.75	ding and laying cement concrete using 20mm and n size granite jelly of ready mixed concrete (RMC)for C works laid in 15cms thick layers and well compacted ting, curing, finishing with necessary cement mortar, works and scaffoldings to withstand pumping of rete, with all lead and lifts etc., complete (exclusive of of steel and fabrication charges.) Ready mixed Cement rete M-20 (1:1.5:3) for raft foundation, column footing, and secondary beams etc complete as per ifications and directions of engineer in charge of the	Cum	5500.0	Rupees Five Thousand Five Hundred Only
9	1230	um De-watering with vaccum pump and suction mat compaction with skin floater clubbed with floating disc ding cost of generator HOM of machinery Screed tiry, Power Floater, blade and disc etc complete as per ifications and directions of engineer in charge of the	Sqm	97.0	Rupees Ninety Seven Only
10	121.5	ding groove cutting for width of 5mm to 10mm and 80mm-100mm including cost of cutting machine, rator and HOM of machinery including cost of blade nt etc including cleaning of groove and providing sand ot bitumne fillars, and filler metal etc., indluding cost of eryance of all materials, labours, lead and lift charges ll other incidental charges as per drawing and as per fication Concrete Pavement etc complete as per ifications and directions of engineer in charge of the	Rmt	124.0	Rupees One Hundred Twenty Four Only
11	1243.6	for Disposal of Debris shall be payable at carriage by Mechanical means inlcuding loading and unloading mplete as per specifications and directions of eer in charge of the work	Cum	73.0	Rupees Seventy Three Only

Signature e Contractor

Executive Engineer.
Byarayanapura Division
BBMP, Bangalore - 92
20/5/16.

20/05 Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92